



FLORIDA DEPARTMENT OF TRANSPORTATION

95 Express Lanes Phase 3C Project

SR 9/I-95 from south of Hollywood Boulevard to south of Broward Boulevard and SR 862/I-595 from SR 7/US 441 to SR 9/I-95

Financial Project ID Numbers: 409354-2-52-01 and 432222-1-52-01

Taft Street at SR 9/I-95 To Close Nightly, July 14—18

As part of the 95 Express Phase 3C project, Taft Street at SR 9/I-95 will be closed in each direction nightly as needed 10 p.m. until 6 a.m., Sunday, July 14 through Thursday, July 18 for Class V coating operations. Once the closure is implemented, motorists will be detoured via North Park Road, Johnson Street, and North 26th Avenue. Signage will be in place to assist motorists.



This project will extend the existing managed lanes north from just south of SR 820/Hollywood Boulevard to just south of SR 842/Broward Boulevard in Broward County. One lane will be added and the High Occupancy Vehicle (HOV) lane will be converted to create two managed lanes in each direction. The number of General Use lanes will remain the same. Other project improvements include construction of the SR 9/I-95 and SR 862/I-595 Direct Connectors between the SR 9/I-95 Managed Lanes and SR 862/I-595, as well as reconstruction, milling, resurfacing, and widening of SR 862/I-595 from SR 7/US 441 to SR 9/I-95 and along SR 9/I-95 from south of SR 820/Hollywood Boulevard to south of SR 842/Broward Boulevard. Additional work includes bridge widening along SR 9/I-95 at several locations, the painting of 17 bridges within project limits, I-95/SR 84 interchange modifications, Integrated Intelligent Transportation System (ITS) installation, including traffic monitoring devices, detectors, and dynamic message signs to optimize traffic operations, tolling/gantry construction, ramp signalization implementation at the interchanges, lighting, signage, and drainage Installation and construction of shoulder-mounted sound walls and retaining walls.

CONTACT INFORMATION

Mark Moshier, P.E. - FDOT Project Manager

Mark.Moshier@dot.state.fl.us or 954-958-7628

Daniela Silva - Community Outreach Specialist

Msilva@corradino.com or 786-441-3088

WEB AND SOCIAL MEDIA

Project website: www.d4fdot.com

Facebook: www.facebook.com/MyFDOTSEFL/

Instagram/X: @MyFDOT_SEFL



Construction Cost: \$457 million

Construction Start: January 2, 2019

Anticipated Completion: Spring 2025

FLORIDA DEPARTMENT OF TRANSPORTATION MISSION STATEMENT

The Department will provide a safe transportation system that ensures the mobility of people and goods, enhances economic prosperity and preserves the quality of our environment and communities.