Florida Department of Transportation

RON DESANTIS
GOVERNOR

3400 West Commercial Boulevard
Fort Lauderdale, Florida 33309

JARED W. PERDUE, P.E.
SECRETARY

For Immediate Release
October 2, 2026

Contact: Guillermo Canedo
(954) 777-4090 | Guillermo.Canedo@dot.state.fl.us

FDOT Treasure Coast Traffic Report

October 2, 2026 – October 9, 2026

MARTIN, ST. LUCIE and INDIAN RIVER COUNTIES, Fla. – Treasure Coast traffic will be affected this week by ongoing construction projects and maintenance work in Martin, St. Lucie, and Indian River counties, FDOT officials report. Please note that any full road, ramp or bridge closures have been highlighted below.
For around-the-clock, real-time I-95 traffic information, visit www.fl511.com. For updated lane closure information, please refer to www.d4fdot.com. Follow us on X and Instagram @MyFDOT_SEFL and on Facebook @MyFDOTSEFL.

CONSTRUCTION PROJECTS
MARTIN COUNTY
(Hobe Sound, Palm City, City of Stuart, Stuart, Jensen Beach, Jupiter Island, Port Salerno, Rio, Indiantown, Tequesta, Town of Sewall's Point)

1. **State Road (S.R.) 9/I-95 from south of S.R. 76/SW Kanner Highway to Martin/St. Lucie County Line Resurfacing, Restoration, and Rehabilitation (RRR) Project**

Description: This 17.002-mile project on S.R. 9/I-95 from north of County Road (C.R.) 708/SE Bridge Road to the Martin/St. Lucie County line began on June 22, 2025. The project improvements consist of milling and resurfacing the S.R. 9/I-95 mainline from north of C.R. 708/SE Bridge Road to the Martin/St. Lucie County line to enhance safety and long-term resiliency; widening the northbound S.R. 9/I-95 entrance ramp shoulder from S.R. 76/SW Kanner Highway to improve safety and traffic operations; constructing new lighting to increase nighttime visibility; installing Wrong Way Vehicle Detection Systems (WWVDS) on S.R. 76/SW Kanner Highway, S.R. 714/SW Martin Highway, and C.R. 713/SW High Meadow Avenue ramps to improve safety; and upgrading signage and pavement markings to enhance safety, functionality, and traffic operations. For more information, please contact Community Outreach Specialist Kim Johnson at 772-801-8736.
Cost/Completion: $40.8 million/Fall 2028
Traffic Impact:

- Southbound S.R. 9/I-95 from C.R. 708/SE Bridge Road to the approach of Bridge 890111 at the Martin/St. Lucie County line, will have two lanes closed, 7:30 p.m.

to 5:30 a.m. Sunday, October 4, through Tuesday, November 24, for signage, milling, and resurfacing.

- Northbound S.R. 9/I-95 from C.R. 708/SE Bridge Road to the approach of Bridge 890111 at the Martin/St. Lucie County line, will have two lanes closed, 8:30 p.m. to 6:30 a.m. Sunday, October 4, through Tuesday, November 24, for milling and resurfacing. Please click here to view the detour flyers for more information.
- **Ramp Closure:** The S.R. 9/I-95 southbound exit ramp to C.R. 713/SW High Meadow Avenue (Exit 102) will be closed from 8 p.m. to 6 a.m. Sunday, October 4, through Thursday, October 8, for wrong way vehicle testing. Motorists will be detoured southbound on S.R. 9/I-95 to the S.R. 76/SW Kanner Highway exit ramp (Exit 101), to eastbound S.R. 76/SW Kanner Highway, to the northbound S.R. 9/I-95 entrance ramp, to the C.R. 713/SW High Meadow Avenue exit ramp (Exit 102). Detour signage will be in place to assist motorists. Only one ramp closure will occur at a time.
- **Ramp Closure:** The S.R. 9/I-95 southbound exit ramp to C.R. 708/SE Bridge Road (Exit 96) will be closed from 8 p.m. to 6 a.m. Sunday, October 4, through Thursday, October 8, for wrong way vehicle testing. Motorists will be detoured from southbound S.R. 9/I-95 at the S.R. 76/SW Kanner Highway exit ramp to southbound C.R. 711/Pratt-Whitney Road to the eastbound C.R. 708/SE Bridge Road. The contingency dates due to weather or other unforeseen circumstances will be Sunday, October 11, through Thursday, October 15. Detour signage will be in place to assist motorists. Only one ramp closure will occur at a time.
- **Ramp Closure:** The S.R. 9/I-95 northbound entrance ramp from C.R. 713/SW High Meadow Avenue will be closed from 8 p.m. to 6 a.m. Sunday, October 4, through Thursday, October 8, for milling and resurfacing. Motorists will be detoured to southbound S.R. 9/I-95 to the S.R. 76/SW Kanner Highway exit ramp (Exit 101), to the S.R. 76/SW Kanner Highway northbound entrance ramp. The contingency dates due to weather or other unforeseen circumstances will be Sunday, October 11, through Thursday, October 15. Detour signage will be in place to assist motorists. Only one ramp closure will occur at a time.
- **Ramp Closure Advanced Notice:** The S.R. 9/I-95 northbound exit ramp to S.R. 714/SW Martin Highway (Exit 110), will be closed from 8 p.m. to 6 a.m. Sunday, October 18, through Thursday, October 22, for repaving operations. Motorists will continue northbound on S.R. 9/I-95 to the SW Becker Road exit ramp (Exit 114), to westbound SW Becker Road, to the southbound S.R. 9/I-95 entrance ramp, to the S.R. 714/SW Martin Highway exit ramp (Exit 110). The contingency dates due to weather or other unforeseen circumstances will be Sunday, October 25, through Thursday, October 29. Detour signage will be in place to assist motorists. Only one ramp closure will occur at a time.
- **Ramp Closure Advanced Notice:** The S.R. 9/I-95 northbound entrance ramp to S.R. 714/SW Martin Highway (Exit 110), will be closed from 8 p.m. to 6 a.m. Sunday, October 18, through Thursday, October 22, for repaving operations. Motorists will travel eastbound S.R. 714/SW Martin Highway, to northbound SW Newfield Parkway to westbound SW Becker Road, to the northbound S.R. 9/I-95 entrance ramp. The contingency dates due to weather or other unforeseen circumstances will be Sunday, October 25, through Thursday,

October 29. Detour signage will be in place to assist motorists. Only one ramp closure will occur at a time.

2. **S.R. A1A from NE Shore Village Terrace to S.R. 732/Jensen Beach Causeway (RRR) Project**

Description: This 2.277-mile project began on March 23, 2026. The project improvements consist of milling and resurfacing of S.R. A1A/NE Ocean Boulevard to extend the service life of the road to provide long-term resiliency, installing new drainage structures to improve stormwater management, widening the shoulders to increase width to five feet at select locations, upgrading the existing lighting at the Jensen Beach Causeway roundabout, upgrading pedestrian curb ramps to comply with Americans with Disabilities Act (ADA) standards for improved safety and connectivity, and installing traffic calming measures and speed feedback signs to enhance safety; and upgrading signage and pavement markings to increase safety, functionality, and traffic operations. For more information, please contact Community Outreach Specialist Kim Johnson at 772-801-8736.
Cost/Completion: $4.9 million/Spring 2027
Traffic Impact:

- Northbound and southbound S.R. A1A/NE Ocean Boulevard from NE Shore Village Terrace to south of S.R. 732/Jensen Beach Causeway, will have one lane closed intermittently, Monday, October 5, through Friday, October 9, for pavement widening and drainage work. During this time, two-way traffic will be maintained by a flagging operation.

3. **State Road (S.R.) 714/SW Martin Highway Restoration, Resurfacing, and Rehabilitation Project from east of SW Stuart West Boulevard to west of Citrus Boulevard**

Description: This 3.314-mile project on S.R. 714/SW Martin Highway from east of SW Stuart West Boulevard to west of Citrus Boulevard, in the city of Palm City and unincorporated Martin County, began in April 2026. The project improvements consist of milling and resurfacing the existing roadway within the project limits to enhance safety and long-term resiliency, widening eastbound and westbound SW Boat Ramp Avenue to accommodate turn lanes, installing new light poles at SW Boat Ramp Avenue to boost nighttime visibility, and upgrading signage and pavement markings to enhance safety, functionality, and traffic operations. For more information, please contact Community Outreach Specialist Kim Johnson at 772-801-8736.
Cost/Completion: $3.5 million/Fall 2026
Traffic Impact:

- Eastbound and westbound S.R. 714/SW Martin Highway between east of SW Stuart W Boulevard and west of Citrus Boulevard, will have one lane closed intermittently, from 7 p.m. to 6 a.m. Sunday, October 4, through Thursday, October 8, for milling and resurfacing. During this time, two-way traffic will be maintained by a flagging operation.

ST. LUCIE COUNTY

(City of Port St. Lucie, Port St. Lucie, White City, City of Fort Pierce, Fort Pierce, Okeechobee, St. Lucie West, Tradition)

4. **State Road (S.R.) 9/I-95 from south of SW Becker Road to south of S.R. 716/SW Gatlin Boulevard & S.R. 716/SW Tradition Parkway**

Description: This 5.070-mile project on State Road (S.R.) 9/I-95 from south of SW Becker Road to south of S.R. 716/SW Gatlin Boulevard & S.R. 716/SW Tradition Parkway, in the city of Port St. Lucie, and unincorporated St. Lucie County will begin in July 2026. The project improvements consist of installing new Intelligent Transportation Systems or (ITS) devices, milling and resurfacing the existing roadway within the project limits to enhance safety and long-term resiliency, replacing the guardrail, and upgrading pavement markings and signage to enhance safety, functionality, and traffic operations. For more information, please contact Community Outreach Specialist Kim Johnson at 772-801-8736.
Cost/Completion: $5.6 million/Fall 2026
Traffic Impact:

- Northbound S.R. 9/I-95 between S.R. 716/SW Gatlin Boulevard (mile marker 118) and just south of SW Becker Road (mile marker 114), will have two lanes closed, with possible lane shifts, from 8 p.m. to 6 a.m. Sunday, October 4, through Friday, October 9, for milling and repaving operations.
- Southbound S.R. 9/I-95 between S.R. 716/SW Gatlin Boulevard (mile marker 118) and just south of SW Becker Road (mile marker 114), will have two lanes closed, with possible lane shifts, from 7:30 p.m. to 5:30 a.m. Sunday, October 4, through Friday, October 9, for milling and repaving operations. Please click here to view the detour flyers for more information.
- **Ramp Closure:** The S.R. 9/I-95 southbound exit ramp to SW Becker Road (Exit 114) will be closed from 7:30 p.m. to 5:30 a.m. Sunday, October 4, through Thursday, October 8, for milling and resurfacing. Motorists will be detoured from S.R. 9/I-95 to the SW Tradition Parkway/SW Gatlin Boulevard exit ramp (Exit 118), to westbound SW Tradition Parkway/SW Gatlin Boulevard to southbound Village Parkway to SW Becker Road. Detour signage will be in place to assist motorists. Only one ramp closure will occur at a time.

5. **State Road (S.R.) 716/SE Port St. Lucie Boulevard and U.S. 1/State Road (S.R.) 5 Resurfacing, Restoration, and Rehabilitation (RRR) Project**

Description: The project began on August 5, 2025. The project improvements consist of milling and repaving the existing roadways within the project limits to enhance safety and long-term resiliency; upgrading signalization at the intersections of Lennard Road, S.R. 716/SE Port St. Lucie Boulevard, SE Morningside Boulevard, and SE Gowin Drive to improve traffic operations; modifying the lane configuration on Lennard Road at U.S. 1/S.R. 5 to enhance safety and traffic operations; upgrading the existing lighting at signalized intersections to LED fixtures throughout the project corridors to increase nighttime visibility; upgrading pedestrian signals with new technology at signalized intersections to improve push button accessibility; reconstructing existing sidewalk curb ramps and replacing damaged sidewalk throughout the project limits to enhance safety and connectivity for pedestrians; upgrading drainage at various locations along S.R.

716/SE Port St. Lucie Boulevard and U.S. 1/S.R. 5 to improve long-term resiliency; restriping U.S. 1/S.R. 5 to provide seven-foot bicycle lanes to enhance safety; and upgrading signage and pavement markings to increase safety, functionality, and traffic operations. For more information, please contact Community Outreach Specialist Kim Johnson at 772-801-8736.
Cost/Completion: $6.8 million/Spring 2027
Traffic Impact:

- Westbound and eastbound S.R. 716/SE Port St. Lucie Boulevard between SE Seafury Lane and SE Lennard Road, will have one lane closed intermittently, 8:30 a.m. to 4:30 p.m. Monday, October 5, through Friday, October 9, for roadway construction and preliminary inspections.
- Southbound and northbound S.R. 5/U.S. 1 between SE Jennings Road and NW Golden Oak Trail, will have one lane closed, 8:30 a.m. to 4:30 p.m. Monday, October 5, through Friday, October 9, for sod installation and roadway construction and preliminary inspections.
- Westbound and eastbound S.R. 716/SE Port St. Lucie Boulevard between SE Seafury Lane and SE Lennard Road, will have two lanes closed intermittently, 8 p.m. to 6 a.m. Sunday, October 4, through Friday, October 9, for roadway construction, thermo striping, and preliminary inspections.
- Southbound and northbound S.R. 5/U.S. 1 between SE Jennings Road and NW Golden Oak Trail, will have one lane closed, 8 p.m. to 6 a.m. Sunday, October 4, through Friday, October 9, for milling and repaving operations, thermo striping, and preliminary inspections.

6. <u>SW Port St. Lucie Boulevard Widening Project from south of SW Paar Drive to south of SW Alcantarra Boulevard</u>

Description: Construction began on Monday, September 8, 2025. The project improvements consist of widening SW Port St. Lucie Boulevard from a two-lane undivided roadway to a four-lane divided roadway, separated by an 18-foot wide median with stamped concrete and landscaping to improve safety and traffic operations; constructing new right-turn lanes on SW Port St. Lucie Boulevard at the north and south approaches to SW Paar Drive to enhance traffic flow; constructing new signalized intersections with mast arms on SW Port St. Lucie Boulevard at SW Paar Drive and SW McCall Road to improve safety and traffic operations; upgrading existing sidewalk curb ramps and constructing a new 8- to 10-foot wide sidewalk along both sides of SW Port St. Lucie Boulevard and adjacent side streets to improve pedestrian safety and connectivity; upgrading the existing lighting to LED fixtures and installing new light poles on the east side of the roadway within the project limits to improve safety for motorists and pedestrians; constructing a new drainage system to enhance functionality and long-term resiliency; and installing signage and pavement markings to improve safety, functionality, and traffic operations. For more information, please contact Community Outreach Specialist Kim Johnson at 772-801-8736.
Cost/Completion: $25.6 million/Fall 2028
Traffic Impact:

- Northbound and southbound SW Port St. Lucie Boulevard between SW Jordin Avenue and SW Alcantarra Boulevard, will have one lane closed intermittently,

from 8 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for roadway construction.

- As part of the SW Port St. Lucie Boulevard Widening Project, extended overnight road closures will occur intermittently on SW Koler Avenue, SW McCall Road, SW McCoy Avenue, and SW Paar Drive, for the installation of drainage and utilities. Closures may begin at 7 a.m. on Monday, October 5, with roads reopening at 5 p.m. on Friday, October 9. Adjacent road closures will not occur at the same time. Access to residences and businesses will be maintained throughout the work. Please click here to view the detour flyers for more information.
    - Eastbound and westbound SW Koler Avenue will be closed between SW Port St. Lucie Boulevard and SW Kober Road. Motorists on northbound SW Port St. Lucie Boulevard will detour to eastbound SW McCall Road to northbound SW Kober Road, to SW Koler Avenue. Motorists on southbound SW Port St. Lucie Boulevard will detour to eastbound SW McComb Avenue, to eastbound SW McCracken Avenue, to southbound SW Lachine Street, to westbound SW Koler Avenue.
    - Eastbound and westbound SW McCall Road will be closed between SW Port St. Lucie Boulevard and SW Kabane Street. Motorists on westbound SW McCall Road will detour to northbound SW Port St. Lucie Boulevard, to westbound SW McHord Road, to southbound SW Kabane Street, to SW McCall Road. Motorists on eastbound SW McCall Road will detour to northbound SW Kabane Street, to eastbound SW McHord Road, to Port St. Lucie Boulevard.
    - Eastbound and westbound SW McCoy Avenue will be closed between SW Port St. Lucie Boulevard and SW Jamros Street. Motorists traveling southbound on SW Port St. Lucie Boulevard will detour to eastbound SW McComb Avenue, to northbound SW Jamros Street, to SW McCoy Avenue. Motorists traveling westbound on SW McCoy Avenue will detour to southbound SW Jamros Street, to westbound SW McComb Avenue, to SW Port St. Lucie Boulevard.
    - Eastbound SW Paar Drive will be closed between SW Port St. Lucie Boulevard and SW McCandless Street. Motorists traveling on northbound SW Port St. Lucie Boulevard will detour to eastbound SW Jordin Avenue, to northbound SW McCrory Street, to westbound SW Jaffe Avenue, to northbound SW McCandless Street, to SW Paar Drive. Motorists traveling on southbound SW Port St. Lucie Boulevard will detour to eastbound SW Jaslo Avenue, to southbound SW McCain Street, to SW Paar Drive.
    - Westbound SW Paar Drive will be closed between SW Port St. Lucie Boulevard and SW Jaqust Street. Motorists traveling on northbound SW Port St. Lucie Boulevard will detour to westbound SW Jordin Avenue, to northbound SW Jaqust Street, to SW Paar Drive. Motorists traveling on southbound SW Port St. Lucie Boulevard will detour to westbound SW McCullough Avenue, to southbound SW McIntyre Street, to westbound SW Jaslo Avenue, to southbound SW Jarmer Road, to SW Paar Drive.

- **Advanced Notice:** As part of the SW Port St. Lucie Boulevard Widening Project, beginning at 9 p.m. to 5 a.m. Tuesday, October 20, and Wednesday, October 21, full road closures will occur intermittently on SW Port St. Lucie Boulevard, for utility operations. Adjacent closures shall not occur simultaneously. Access to residences and businesses will be maintained. Please click here to view the detour flyers for more information.
    - Northbound and southbound SW Port St. Lucie Boulevard will be closed between SW McCracken Avenue and SW McCoy Avenue. Motorists traveling northbound on SW Port St. Lucie Boulevard will detour to eastbound SW McComb Avenue to northbound SW Jamros Street to westbound SW McCoy Avenue to SW Port St. Lucie Boulevard. Motorists traveling southbound on SW Port St. Lucie Boulevard to eastbound SW McCoy Avenue to southbound SW Jamros Street to westbound SW McComb Avenue to SW Port St. Lucie Boulevard.

7. State Road (S.R.) 9/I-95 Roadway Improvement Project north of Glades Cut-Off Road to north of Florida's Turnpike/S.R. 91

Description: This 2.756-mile project on State Road (S.R.) 9/I-95 Roadway Improvement Project, north of Glades Cut-Off Road to north of Florida's Turnpike/S.R. 91, in the city of Fort Pierce, and unincorporated St. Lucie County will begin in June 2026. The project improvements consist of installing new Intelligent Transportation Systems or (ITS) devices, milling and resurfacing the existing roadway within the project limits to enhance safety and long-term resiliency, replacing the guardrail, and upgrading pavement markings and signage to enhance safety, functionality, and traffic operations. For more information, please contact Community Outreach Specialist Kim Johnson at 772-801-8736.

Cost/Completion: $5.1 million/Spring 2027

Traffic Impact:

- Northbound and southbound S.R. 9/I-95 between Glades Cut Off Road (mile marker 123) and just south of S.R. 70/Okeechobee Road (mile marker 128), will have the shoulder lanes closed from 6:30 a.m. to 7 p.m. Sunday, October 4, through Friday, October 9, as needed, for guardrail, ITS, and drill shaft operations.

8. State Road (S.R.) A1A North Causeway Over the Intracoastal Waterway (ICWW) Bridge Replacement Project

Description: This project began on May 1, 2023. The S.R. A1A North Causeway Over the Intracoastal Waterway (ICWW) Bridge Replacement project improvements consist of constructing a new high-level fixed bridge connected directly to U.S. 1/S.R. 5 going over the Florida East Coast (FEC) Railroad, County Road (C.R.) 605/Old Dixie Highway, and the Intracoastal Waterway (ICWW) featuring: one 12-foot travel lane in each direction, navigational clearances of 85 feet vertical and 125 feet horizontal at the waterway channel, installing a barrier-protected 8-foot sidewalk on the south side of the bridge and a barrier-protected 12-foot shared use path on the north side of the bridge, installing 7-foot buffered bicycle lanes within the shoulders on both sides of S.R. A1A, constructing a 12-foot shared-use path along C.R. 605/Old Dixie Highway to provide

connectivity to the East Coast Greenway, building an observation deck beneath the west side of the new bridge structure, constructing a new access road under the bridge to businesses east of the FEC Railroad, extending Juanita Avenue from U.S. 1/S.R. 5 to C.R. 605/Old Dixie Highway, and connecting U.S. 1/S.R. 5 and C.R.605/Old Dixie Highway along Sunny Lane. For more information, please contact Community Outreach Specialist Samantha Kayser at 772-579-5479.
Cost/Completion: $111.5 million/Late 2027
Channel Impact:

- As of 6 p.m. on August 8, 2026, the drawbridge operation regulation is obsolete and is no longer being enforced. The new fixed high-level S.R. A1A/E.C. Summerlin Family Bridge now spans the navigable channel, which permanently limits the vertical clearance to 85 feet at mean high water. All mariners should exercise caution and navigate the area at a slow speed. For waterway issues, please contact the USCG Sector Miami Waterways Division at 305-535-4317 or sectormiamiwaterways@uscg.mil.
- **Partial Channel Closures – Monday, August 31 – Monday, December 1, 2026:** The new high-level fixed S.R. A1A/E.C. Summerlin Family Bridge opened to motorists on Friday, May 15, 2026, and spans the navigable channel which permanently limits the vertical clearance to 85 feet at mean high water. Demolition of the bascule bridge is ongoing. The bascule piers will be removed from the waterway utilizing cofferdams. The navigation channel will be partially obstructed beginning Monday, August 31, 2026, through Monday, December 1, 2026, as follows:
    - Beginning Monday, August 31 through Wednesday, September 9, 2026, the channel will be partially obstructed providing 50 feet of horizontal clearance for the passage of vessels.
    - From Wednesday, September 9 through Monday, September 14, 2026, the channel will be partially obstructed providing 40 feet of horizontal clearance for the passage of vessels between the hours of 7 a.m. and 5 p.m., daily. A full channel passage will be available with one hour notice to the on-scene tug "MANDI" on VHF-FM marine radio channel 13. Outside work hours, 85 feet of horizontal clearance will be available.
    - From Monday, September 14 through Wednesday, September 23, 2026, the channel will be partially obstructed providing 40 feet of horizontal clearance for the passage of vessels.
    - From Wednesday, September 23 through Monday, December 1, 2026, the channel will be partially obstructed providing 40 feet of horizontal clearance for the passage of vessels between the hours of 7 a.m. and 5 p.m., daily. A full channel passage will be available with 1 hour notice to the on-scene tug "MANDI" on VHF-FM marine radio channel 13. Outside work hours, 85 feet of horizontal clearance will be available.
    - A temporary work trestle (platform) has been installed on the northeast side of the bridge. In water work continues directly adjacent to and across the navigable waterway with barge(s) in order to perform other associated construction activities.

    - All in-water equipment will be properly lighted. All mariners are requested to use caution and transit the area at a slow speed.
    - For waterways questions, please contact the USCG Sector Miami Waterways Division at 305-535-4317 or sectormiamiwaterways@uscg.mil.

Traffic Impact:

- Signal operations may be impacted by project activities and are being monitored closely during construction for temporary adjustments to reduce congestion.
- The new S.R. A1A North Causeway Bridge over the ICWW connecting directly to U.S. 1/S.R. 5 opened to the traveling public on Friday, May 15, 2026. At opening:
    - The eastbound and westbound S.R. A1A bicycle lanes and the shared-use path along S.R. A1A on the north side of the bridge remain closed as construction activities continue. Pedestrians are detoured to the sidewalk on the south side of the bridge.
    - The observation deck at the west end of the new bridge is also closed during this construction phase.
    - The existing drawbridge was permanently closed to vehicular traffic and demolished as part of the final phase of work through Late 2027.
    - Please note that the new bridge does not connect to C.R. 605/Old Dixie Highway.
    - Accessing U.S. 1/S.R. 5 and C.R. 605/Old Dixie Highway:
        - Motorists traveling along U.S. 1/S.R. 5 can access C.R. 605/Old Dixie Highway via Juanita Avenue.
        - Motorists traveling along C.R. 605/Old Dixie Highway can access northbound and southbound U.S. 1/S.R. 5 via Juanita Avenue and northbound U.S. 1/S.R. 5 only via Sunny Lane. Please click here to view the graphic.
- U.S. 1/S.R. 5 between the Juanita Avenue intersection and Naco Road will have one northbound lane closed, 9 a.m. to 5 p.m., Monday through Friday, through October 2026, for roadway construction.
- To enhance safety and long-term resiliency, the S.R. A1A and C.R. 605/Old Dixie Highway intersection was shifted slightly south on Monday, April 28, 2025, to facilitate the construction of the west end of the new North Causeway Bridge. Please note that the traffic lights at the S.R. A1A and C.R. 605/Old Dixie Highway intersection were removed and replaced with a 2-way stop.
- To enhance safety and long-term resiliency, eastbound and westbound traffic on S.R. A1A east of the park was shifted approximately 25 feet to the north on July 21, 2025. This shift is expected to last through October 2026 to allow for permanent roadway construction.
- Northbound and southbound traffic on C.R. 605/Old Dixie Highway, approximately 200 feet from the S.R. A1A intersection was shifted slightly to the west on Monday, Aug. 4, 2025, for pile driving work adjacent to the railroad tracks.
- Juanita Avenue east of U.S. 1/S.R. 5 is open to motorists. The new traffic signal at the intersection of Juanita Avenue and U.S. 1/S.R. 5 is activated.

- Juanita Avenue west of U.S. 1/S.R. 5 will have the westbound lane closed, 9 a.m. to 5 p.m., Monday through Friday, through October 2026, for installation of drainage catch basins. A flagging operation will be in place to assist motorists.
- Harbortown Drive will have one lane closed in either direction, 7 a.m. to 5 p.m., Monday through Friday, through October 2026, for roadway construction. A flagging operation will be in place to assist motorists.
- U.S. 1/S.R. 5 between NE 3rd Street and the Juanita Avenue intersection will have one northbound lane closed, 9 a.m. to 5 p.m., Monday through Friday, through October 2026, for roadway construction and right turn lane extension.
- C.R. 605/Old Dixie Highway between Sunny Lane and Juanita Avenue will have one lane in either direction closed, 7 a.m. to 5 p.m., Monday through Friday, through October 2026, for roadway reconstruction. A flagging operation will be in place to maintain local traffic.
- Marina Access from C.R. 605/Old Dixie Highway to the North Causeway Bridge will have one lane closed in either direction, Monday through Friday, through October 2026, for roadway construction. A flagging operation will be in place to maintain local traffic.
- Northbound and southbound U.S. 1/S.R. 5 from the Taylor Creek Bridge to 500 feet north of Juanita Avenue will have one lane closed in either direction, 9 a.m. to 5 p.m., Monday through Friday, through October 2026, for roadway construction.
- Juanita Avenue, east of U.S. 1/S.R. 5, will have one westbound turn lane closed, 9 a.m. to 5 p.m., Monday through Friday, through October 2026, for roadway work. A flagging operation will be in place to assist motorists.
- Eastbound and westbound S.R. A1A, from east of the new E.C. Summerlin Family Bridge to Little Jim's Bridge, will have one lane closed in either direction, 7 a.m. to 5 p.m., Monday through Saturday, beginning Monday, Oct. 5 through Saturday, Oct. 31, for roadway construction. A flagging operation will be in place to assist motorists.

9. <u>County Road (C.R.) 712/Midway Road Widening Project from west of Jenkins Road to Selvitz Road</u>

Description: This 0.785-mile project began on April 1, 2024. The project improvements include widening C.R. 712/Midway Road from a two-lane undivided roadway to a four-lane divided roadway. The eastbound and westbound lanes of C.R. 712/Midway Road will be separated by a raised landscaped median. Additional improvements include constructing left turn lanes in the median to allow access to adjacent side streets, properties and businesses, constructing 7-foot buffered bicycle lanes on both sides of C.R. 712/Midway Road, constructing a 6-foot sidewalk along the north side of C.R. 712/Midway Road, constructing a 12-foot bicycle/pedestrian path along the south side of the project, installing landscaping along the south side of the project, and upgrading drainage, signage and pavement markings. For more information, please contact Community Outreach Specialist Kim Johnson at 772-801-8736.
Cost/Completion: $23.5 million/Early 2027
Traffic Impact:

- Eastbound or westbound C.R. 712/Midway Road between Florida's Turnpike and Selvitz Road, will have one lane closed intermittently, 9 a.m. to 4 p.m. Monday through Friday, through October 2026, to facilitate roadway reconstruction.
- As part of the C.R. 712/Midway Road Widening Project, westbound traffic was shifted north onto the newly constructed lanes, between NW Corporate Way and Selvitz Road. The shift began on Wednesday, June 10, and is expected to remain in place through October 2026. Please be advised that this schedule may change due to weather or unforeseen circumstances. The implementation of this traffic shift allows for the safe progression of the roadway construction on the median of C.R. 712/Midway Road.

INDIAN RIVER COUNTY
(City of Vero Beach, Vero Beach, Indian River Shores, Sebastian, Wabasso, Wabasso Beach, City of Fellsmere)

10. State Road (S.R.) 9/I-95 at S.R. 606/Oslo Road New Interchange and S.R. 606/Oslo Road Widening Project

Description: This project began on August 14, 2023. In partnership with Indian River County, FDOT is pleased to announce the construction of the new interchange at S.R. 9/I-95 and S.R. 606/Oslo Road and S.R. 606/Oslo Road improvements. Additionally, S.R. 606/Oslo Road will have capacity improvements to four lanes from west of S.R. 9/I-95 to 58th Avenue per Indian River County Resolution Nos. 2017-022 and 2017-023. Project improvements consist of constructing a new interchange with partial cloverleaf ramps at S.R. 9/I-95 and S.R. 606/Oslo Road, widening S.R. 606/Oslo Road from a two-lane to a four-lane divided roadway from west of S.R. 9/I-95 to SW 58th Avenue, installing interchange ramp lighting, replacing the existing S.R. 606/Oslo Road bridge over S.R. 9/ I-95, installing a new signalized intersection at S.R. 606/Oslo Road and 66th Avenue SW, installing intersection lighting at 74th Avenue, 66th Avenue, and 58th Avenue, realigning 82nd Avenue at S.R. 606/Oslo Road, eliminating the 86th Avenue connection to S.R. 606/Oslo Road, constructing 13th Street SW to connect 86th Avenue SW and 90th Avenue, extending the south limit the existing noise wall on S.R. 9/I-95, replacing Indian River County sanitary, water and raw water mains, upgrading signing, signalization, intersection lighting, bicycle lanes, and sidewalks, installing a closed drainage system and constructing three drainage ponds. For more information, please contact Community Outreach Specialist Samantha Kayser at 772-579-5479.
Cost/Completion: $95.78 million/Spring 2027
Traffic Impact:

- Eastbound and westbound S.R. 606/Oslo Road, from approximately 1,500 feet west of the S.R. 606/Oslo Road bridge over S.R. 9/I-95 to SW 58th Avenue, may have one lane closed in each direction, as needed, through October 2026, for sod installation, thermoplastic pavement marking placement, addressing punch list items, and project site clean up. One travel lane will remain open in each direction, and the lane closures may alternate as needed.
- Northbound and southbound 66th Avenue, from the intersection of S.R. 606/Oslo Road to approximately 600 feet north of the S.R. 606/Oslo Road intersection, may have one lane closed nightly, 9 p.m. to 6 a.m., Sunday through Thursday,

through October 2026, for sod installation, thermoplastic pavement marking placement, addressing punch list items, and project site clean up. One travel lane will remain open in each direction, and the lane closures may alternate as needed. Flaggers will be in place to maintain two-way traffic and safely guide motorists through the work zone.

- Northbound and southbound 74th Avenue, from the S.R. 606/Oslo Road intersection to approximately 50 feet north of the S.R. 606/Oslo Road intersection, may have one lane closed nightly, from 9 p.m. to 6 a.m., Sunday through Thursday, through October 2026, for thermoplastic pavement marking placement, punch list work, and project site clean up. Flaggers will be in place to maintain two-way traffic and safely guide motorists through the work zone.
- Northbound and southbound 82nd Avenue, from the S.R. 606/Oslo Road intersection to approximately one mile north of the S.R. 606/Oslo Road intersection, may have one lane closed nightly, from 9 p.m. to 6 a.m., Sunday through Thursday, through October 2026, for thermoplastic pavement marking placement, punch list work, and project site clean up. Flaggers will be in place to maintain two-way traffic and safely guide motorists through the work zone.
- 58th Avenue at the S.R. 606/Oslo Road intersection may have one lane closed in either direction, 9 p.m. to 6 a.m., Sunday through Thursday, through October 2026, for thermoplastic pavement marking placement, punch list work, and project site clean up. Flaggers will be in place to maintain two-way traffic and safely guide motorists through the work zone.
- Northbound and southbound S.R. 9/I-95, within the project limits, may have up to two lanes closed nightly, as needed, from 9 p.m. to 6 a.m., Sunday through Thursday, through October 2026, for thermoplastic pavement marking placement, Wrong Way Vehicle Detection system testing, rumble strip placement, and punch list work.

11. U.S. 1/State Road (S.R.) 5 Sidewalk Improvement Project

Description: This project began on May 29, 2025. The project improvements include installing a six-foot wide concrete sidewalk on the east side of U.S. 1/S.R. 5 from County Road (C.R.) 611/45 Street to south of 53 Street to enhance safety and connectivity for pedestrians, constructing crosswalks at U.S. 1/S.R. 5 and 45 Street to increase pedestrian safety, replacing drainage at various locations throughout the project limits to improve functionality and long-term resiliency, and upgrading signage and pavement markings to boost safety, functionality, and traffic operations. For more information, please contact Community Outreach Specialist Kim Johnson at 772-801-8736.

Cost/Completion: $5.7 million/Fall 2026

Traffic Impact:

- All lanes are open.

12. State Road (S.R.) 510/85 Street Widening Project

Description: The project began on October 29, 2025. The project improvements consist of widening S.R. 510/85 Street from a two-lane undivided roadway to a four-lane divided roadway to improve safety and traffic operations; installing seven-foot wide

buffered bicycle lanes to increase safety; constructing a six-foot wide sidewalk throughout the project limits to enhance pedestrian safety and connectivity; installing new traffic signals at the existing signalized intersections along S.R. 510/85 Street and S.R. 512/Sebastian Boulevard, Mako Way, Hammerhead Way, and 87 Street to improve traffic operations; constructing a new bus transfer facility with six additional bus bays around the perimeter of the new retention pond to improve traffic flow; constructing a new closed drainage system with a retention pond and new utility systems to improve functionality and long-term resiliency; and installing signage and pavement markings to enhance safety, functionality, and traffic operations. For more information, please contact Community Outreach Specialist Kim Johnson at 772-801-8736.
Cost/Completion: $24.89 million/Fall 2028
Traffic Impact:

- Northbound and southbound S.R. 510/90 Avenue between S.R. 512/Sebastian Boulevard and 87 Street, will have one lane closed intermittently, from 8 p.m. to 6 a.m. Sunday, October 4, through Friday, October 9, for roadway construction.
- Southbound S.R. 510/90 Avenue at the Sebastian River High School, the entrance to Hammerhead Way, will be closed from 8 a.m. to 4 p.m. Saturday, October 3, and Sunday, October 4, for repaving operations. Access to Sebastian River High School will be maintained.

13. State Road (S.R.) A1A/Jimmy Buffett Memorial Highway Over Sebastian Inlet Bridge Replacement Project

Description: The project began on June 1, 2026. Project improvements consist of constructing a new fixed bridge east of the existing bridge with a vertical clearance of 51 feet, two 12-foot wide travel lanes, two 8-foot wide shoulders, and two 12-foot wide shared-use paths to enhance safety, long-term resiliency, and pedestrian connectivity; constructing two observation decks, one under the bridge from the south shore and one under the bridge from the north shore to enhance recreational enjoyment for the community; constructing crosswalks on S.R. A1A/Jimmy Buffett Memorial Highway at the State Park's north and south entrances to enhance safety and pedestrian connectivity; reconfiguring the State Park's north and south entrances, including the addition of exiting right-turn lanes to improve traffic operations; constructing a southbound acceleration lane on S.R. A1A/Jimmy Buffett Memorial Highway from the State Park's south entrance to improve traffic operations; lengthening the southbound S.R. A1A/Jimmy Buffett Memorial Highway right-turn lane, north and south of the bridge into the State Park to improve traffic operations; constructing a 12-foot wide shared-use path on both sides of the bridge and roadway to enhance safety and pedestrian connectivity; and milling and resurfacing the State Park's North and South Parking Lots to enhance long-term resiliency. For more information, please contact Community Outreach Specialist Samantha Kayser at 772-579-5479.
Cost/Completion: $101.9 million/Spring 2032
Traffic Impact:

- **Advanced Notice – Traffic Shift:** To enhance safety and long-term resiliency, northbound and southbound traffic on S.R. A1A/Jimmy Buffett Memorial Highway will be shifted from south of the Sebastian Inlet Bridge in Indian River County to north of the Sebastian Inlet Bridge in Brevard County beginning at approximately

7 a.m. (subject to change) on Tuesday, October 13, 2026, weather permitting, through Late 2028. The traffic shift is necessary to safely and efficiently complete critical construction activities, including bridge and roadway construction, and temporary and permanent wall construction. If weather or unforeseen circumstances occur, the shift will take place by Thursday, Oct. 22. Please view the attached flyer for more information.
    - Starting approximately 1,400 feet south of the Sebastian Inlet State Park entrance in Indian River County, both northbound and southbound traffic on S.R. A1A/Jimmy Buffett Memorial Highway will shift onto temporary pavement on the west side of the existing roadway. Traffic will shift back to the existing roadway when crossing over the Sebastian Inlet Bridge. On the north side of the existing bridge, northbound and southbound traffic on S.R. A1A/Jimmy Buffett Memorial Highway will shift to temporary pavement west of the existing roadway, then east onto temporary pavement for approximately 900 feet, before shifting west onto the existing roadway.
    - Signage will be in place to assist motorists and pedestrians.
- S.R. A1A/Jimmy Buffett Memorial Highway, from the Sebastian Inlet State Park South Entrance in Indian River County to the Sebastian Inlet State Park North Entrance in Brevard County, may have one northbound lane and/or shoulder closed, as needed, Monday through Thursday from 7 a.m. to 5 p.m., and Friday from 7 a.m. to 1 p.m., through October 2026, excluding Saturdays, Sundays, and holidays, for roadway construction activities. Only one lane will be closed at a time, and flaggers will direct traffic through the work zone. Motorists should use caution and allow extra travel time.
- S.R. A1A/Jimmy Buffett Memorial Highway, from the Sebastian Inlet State Park South Entrance in Indian River County to the Sebastian Inlet State Park North Entrance in Brevard County, may have one southbound lane and/or shoulder closed, as needed, Monday through Thursday from 7 a.m. to 5 p.m., and Friday from 7 a.m. to 1 p.m., through October 2026, excluding Saturdays, Sundays, and holidays, for cut/fill operations. Only one lane will be closed at a time, and flaggers will direct traffic through the work zone. Motorists should use caution and allow extra travel time.
- To enhance safety and long-term resiliency, crews will perform clearing and grubbing activities at the Sebastian Inlet State Park North Parking Lot within the Florida Department of Transportation (FDOT) right-of-way, as needed, 7 a.m. to 5 p.m., Monday through Thursday, and Friday, 7 a.m. to 1 p.m., through October 2026. A flagging operation will be in place to maintain traffic.
- **Partial Closure of Sebastian Inlet State Park – North Parking Lot:** To enhance safety and long-term resiliency, the south section of the Sebastian Inlet State Park North Parking Lot is partially closed around-the-clock through Spring 2032 for bridge construction activities. Signage will be in place to assist motorists and pedestrians. Please click here to view the flyer for more information.
    - The State Park and remaining portions of the North Parking Lot will remain open for public use.

    - Limited parking will be available west of the bridge, south of the State Park entrance.
    - One row of public parking will remain open east of the bridge, along with the parking area northeast of the State Park entrance.
    - The observation deck under the north side of the bridge will remain closed.
- **Partial Closure of Sebastian Inlet State Park – South Parking Lot:** To enhance safety and long-term resiliency, sections of the Sebastian Inlet State Park South Parking Lot, located beneath and to the east and west of the bridge, were partially closed around-the-clock beginning at 7 a.m. Thursday, June 4, 2026, through Spring 2032, for bridge construction activities. Signage is in place to assist motorists and pedestrians. Please click here to view the flyer for more information.
    - Access to the south jetty from the South Parking Lot is closed.
    - The State Park and remaining portions of the South Parking Lot remain open for public use.
    - Limited parking is available west of the bridge inside the park.
    - The observation deck under the south side of the bridge remains closed.
    - Access to the boat ramp will be maintained at all times.

MAINTENANCE, UTILITY, PERMIT and ADDITIONAL AGENCY PROJECTS

For additional maintenance, utility, permit, and agency closures not listed below, please click this link: Lcisv2

MARTIN COUNTY

(Hobe Sound, Palm City, City of Stuart, Stuart, Jensen Beach, Jupiter Island, Port Salerno, Port Mayaca, Rio, Indiantown, Tequesta, Town of Sewall's Point)

HOBE SOUND:

Northbound S.R. 5/U.S. 1 between SE Turn Leaf Circle & SE Heritage Boulevard, in Hobe Sound, will have 1 of 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L utility operations. For more information, please contact Rafael Ureña at 772-882-5084.

PALM CITY:

Westbound S.R. 718/SW Martin Highway between SW Martin Downs Boulevard & SW 42 Avenue, in Palm City, will have 1 of 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L utility installation. For more information, please contact Rafael Ureña at 772-882-5084.

STUART:

Northbound S.R. 76/SW Kanner Highway between SW Gaines Avenue & SW Salerno Road, in Stuart, will have 1 of 3 lanes closed intermittently, with possible lane shifts, 9

a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L utility operations. For more information, please contact Rafael Ureña at 772-882-5084.

Southbound NE Ocean Boulevard/Jimmy Buffet Memorial Highway between Joe's Point Road & Tiger Shores Beach, in Stuart, will have 1 of 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L utility operations. For more information, please contact Rafael Ureña at 772-882-5084.

PORT MAYACA:

Northbound & southbound SW Conners Highway between Port Mayaca Polo Club & Florida Trail Port Mayaca Recreation Area Trailhead, in Port Mayaca, will have 1 lane in either direction closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L utilities installation. For more information, please contact Rafael Ureña at 772-882-5084.

ST. LUCIE COUNTY
(City of Port St. Lucie, Port St. Lucie, White City, City of Fort Pierce, Fort Pierce, Okeechobee, St. Lucie West, Tradition)

PORT ST. LUCIE:

Eastbound & westbound SW Port St. Lucie Boulevard between SW Monterey Lane & SW Bayshore Boulevard, in Port St. Lucie, will have 1 of 4 lanes closed intermittently, with possible lane shifts, 9 p.m. to 4 a.m. Monday, October 5, through Friday, October 9, for utility operations. For more information, please contact Nicholas McConnell at 772-584-4530.

Eastbound & westbound SW Port St. Lucie Boulevard between SE Whitmore Drive & SE Wald Street, in Port St. Lucie, will have 1 of 4 lanes closed intermittently, with possible lane shifts, 9 p.m. to 4 a.m. Monday, October 5, through Friday, October 9, for utility operations. For more information, please contact Nicholas McConnell at 772-584-4530.

Eastbound & westbound SW Port St. Lucie Boulevard between SW Trenton Lane & SW Cameo Boulevard, in Port St. Lucie, will have 1 of 4 lanes closed intermittently, with possible lane shifts, 9 p.m. to 4 a.m. Monday, October 5, through Friday, October 9, for utility operations. For more information, please contact Nicholas McConnell at 772-584-4530.

Eastbound & westbound SW Port St. Lucie Boulevard between SE Midport Road & SE Westmoreland Road, in Port St. Lucie, will have 1 of 4 lanes closed intermittently, with possible lane shifts, 9 p.m. to 4 a.m. Monday, October 5, through Friday, October 9, for utility operations. For more information, please contact Nicholas McConnell at 772-584-4530.

Eastbound & westbound SW Port St. Lucie Boulevard between SE Delano Road & SE Morningside Boulevard, in Port St. Lucie, will have 1 of 4 lanes closed intermittently, with possible lane shifts, 9 p.m. to 4 a.m. Monday, October 5, through Friday, October 9, for utility operations. For more information, please contact Nicholas McConnell at 772-584-4530.

Eastbound & westbound SW Port St. Lucie Boulevard between SE Gowin Drive & SE Lanewood Street, in Port St. Lucie, will have 1 of 4 lanes closed intermittently, with possible lane shifts, 9 p.m. to 4 a.m. Monday, October 5, through Friday, October 9, for utility operations. For more information, please contact Nicholas McConnell at 772-584-4530.

Northbound NW Federal Highway/U.S. 1 between SE Huffman Road & Savanna Club Road, in Port St. Lucie, will have 1 of 3 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L utility removal. For more information, please contact Rudy Mack at 941-748-8080.

Northbound NW Federal Highway/U.S. 1 between SE Jennings Road & SE Village Drive, in Port St. Lucie, will have 1 of 3 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L utility removal. For more information, please contact Rafael Ureña at 772-882-5084.

Eastbound & westbound C.R. 712/W Midway Road between NW East Torino Parkway & NW Corporate Way in Port St. Lucie, will have 1 of 3 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L utility installations. For more information, please contact Rafael Ureña at 772-882-5084.

Westbound S.R. 70 between Sneed Road & S Header Canal Road in Port St. Lucie, will have 1 of 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L utility installations. For more information, please contact Rafael Ureña at 772-882-5084.

FORT PIERCE:

Northbound S.R. 9/I-95 over S.R. 713/Kings Highway between Orange Avenue & the St. Lucie County rest stop, in Fort Pierce, will have 1 of 4 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Tuesday, October 6, & Wednesday, October 7, for light pole installation. For more information, please contact Tomas Feliciano 954-547-2597.

Northbound & southbound NW Federal Highway/U.S. 1 between Ulrich Road & Tropical Isles Way, in Fort Pierce, will have 1 of 3 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for sign installation. For more information, please contact Bobby Biskupiak at 561-762-5709.

Northbound & southbound S.R. 713/S Kings Highway between Graham Road & Orange Avenue, in Fort Pierce, will have 1 lane in either direction closed intermittently,

with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for milling operations. For more information, please contact Juan Valencia at 786-436-6811.

Southbound S.R. 5/U.S. 1 between Valley Lane & Riverview Memorial Park, in Fort Pierce, will have 1 lane in either direction closed intermittently, with possible lane shifts, 9 a.m. to 3 p.m. Tuesday, October 6, through Friday, October 9, for milling operations. For more information, please contact Gene Horne at 904-860-0072.

Northbound S.R. 5/U.S. 1 at Juanita Avenue, the westbound turning lane, in Fort Pierce, will have 1 lane in either direction closed intermittently, with possible lane shifts, 9 a.m. to 3 p.m. Tuesday, October 6, through Friday, October 9, for milling operations. For more information, please contact Gene Horne at 904-860-0072.

Eastbound & westbound S.R. A1A/Seaway Drive between N 2 Street & Indian River Drive, in Fort Pierce, will have 1 lane in either direction closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for milling operations. For more information, please contact Juan Valencia at 786-436-6811.

Northbound & southbound S.R. A1A/S Ocean Drive between Blind Creek Beachside North & Watersong Way, in Fort Pierce, will have 1 lane in either direction closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for milling operations. For more information, please contact Rafael Ureña at 772-882-5084.

Eastbound & westbound Indrio Road between Aico Road & Koblegard Road/Spanish Lakes Boulevard, in Fort Pierce, will have 1 of 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for sign installation. For more information, please contact Rafael Ureña at 772-882-5084.

Eastbound & westbound S.R. 70/Okeechobee Road between 11 Mile Road & C.R. 712/W Midway Road, in Fort Pierce, will have 1 of 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L pole replacement operations. For more information, please contact Rafael Ureña at 772-882-5084.

Westbound S.R. 70/Okeechobee Road between Coolidge Road & S Rock Road, in Fort Pierce, will have 1 of 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L pole replacement operations. For more information, please contact Rafael Ureña at 772-882-5084.

Eastbound S.R. 70/Okeechobee Road between Gordy Road & Matthews Road, in Fort Pierce, will have 1 of 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L pole replacement operations. For more information, please contact Rafael Ureña at 772-882-5084.

Northbound and southbound NW Federal Highway/U.S. 1 between Sandhill Boulevard & High Point Boulevard, in Fort Pierce, will have 1 lane closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9,

for signalization upgrades. For more information, please contact Kevin Hoo at 240-354-6652.

Northbound and southbound NW Federal Highway/U.S. 1 between Pinewood Drive & Georgia Avenue, in Fort Pierce, will have 1 lane closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for signalization upgrades. For more information, please contact Kevin Hoo at 240-354-6652.

OKEECHOBEE:

Northbound & southbound SW Conners Highway between 138 Boulevard & SW Wood Street, in Okeechobee, will have 1 lane in either direction closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for milling operations. For more information, please contact Rafael Ureña at 772-882-5084.

INDIAN RIVER COUNTY
(City of Vero Beach, Vero Beach, Indian River Shores, City of Sebastian, Sebastian, Wabasso, Wabasso Beach, Orchid Island, City of Fellsmere)

VERO BEACH:

Eastbound S.R. 60/20 Street between 66 Avenue & Indian Creek Boulevard, in Vero Beach, will have 1 of 3 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for utility operations. For more information, please contact Joshua Mobley at 863-677-4748.

Eastbound S.R. 60/20 Street between 94 Court & Americana Way, in Vero Beach, will have 1 of 3 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for utility operations. For more information, please contact Joshua Mobley at 863-677-4748.

Eastbound S.R. 60/20 Street between Indian Creek Boulevard & 63 Court, in Vero Beach, will have 1 of 3 lanes closed intermittently, with possible lane shifts, 9 p.m. to 6 a.m. Monday, October 5, through Friday, October 9, for utility operations. For more information, please contact Gene Horne at 904-860-0072.

Eastbound S.R. 60 between 53 Avenue & 43 Avenue, in Vero Beach, will have 1 of 3 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L utility operations. For more information, please contact Rafael Ureña at 772-882-5084.

Eastbound S.R. 60 between 58 Avenue & 56 Avenue, in Vero Beach, will have 1 of 3 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L utility operations. For more information, please contact Rafael Ureña at 772-882-5084.

Southbound S.R. 5/U.S.1 between 15 Place & 12 Street, in Vero Beach, will have 1 of 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October

5, through Friday, October 9, for FP&L utility operations. For more information, please contact Rafael Ureña at 772-882-5084.

Southbound S.R. 5/U.S.1 between Glendale Road/8 Street & Indian River Boulevard/4 Street, in Vero Beach, will have 1 of 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for utility operations. For more information, please contact Kyle Stark at 321-313-5498.

Northbound S.R. 5/U.S. 1 between Bridge Boulevard & Durrance Road, in Vero Beach, will have 1 of 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for sign installation. For more information, please contact Rafael Ureña at 772-882-5084.

Northbound S.R. 5/U.S. 1 between S Tropicana Drive & Lazy Lane, in Vero Beach, will have 1 of 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for sign installation. For more information, please contact Rafael Ureña at 772-882-5084.

Northbound S.R. 5/U.S. 1 between 61 Place & 63 Street, in Vero Beach, will have 1 of 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for sign installation. For more information, please contact Rafael Ureña at 772-882-5084.

Southbound S.R. A1A between Morning Line Drive & Spyglass Lane, in Vero Beach, will have 1 lane closed intermittently in either direction, for a flagging operation, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, FP&L utilities installation. For more information, please contact Rafael Ureña at 772-882-5084.

Southbound S.R. A1A between W Sandpointe Lane & Sears Cove, in Vero Beach, will have 1 lane closed intermittently in either direction, for a flagging operation, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, FP&L utilities installation. For more information, please contact Rafael Ureña at 772-882-5084.

Northbound & southbound S.R. A1A between Mango Road & Shoe Drive, in Vero Beach, will have 1 lane closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for signalization upgrades. For more information, please contact Kevin Hoo at 240-354-6652.

Northbound & southbound S.R. A1A between Turtle Cove Lane & Lantana Lane, in Vero Beach, will have 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for utility operations. For more information, please contact Kyle Stalk at 321-313-5498.

Eastbound & westbound S.R. 606/Oslo Road between Timber Ridge Trail SW & 9 Avenue SW, in Vero Beach, will have 1 of 2 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for sign installation. For more information, please contact Rafael Ureña at 772-882-5084.

INDIAN RIVER SHORES:

Northbound S.R. A1A between Surf Lane & Seminole Lane, in Indian River Shores, will have 1 lane closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for utility installation. For more information, please contact Brad Searcy at 772-473-2201.

SEBASTIAN:

Northbound NW Federal Highway/U.S. 1 between Jefferson Street & Davis Street, in Sebastian, will have 1 of 3 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L utility operations. For more information, please contact Rafael Ureña at 772-882-5084.

Southbound NW Federal Highway/U.S. 1 between 143 Street & Jackson Street, in Sebastian, will have 1 of 3 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L utility operations. For more information, please contact Rafael Ureña at 772-882-5084.

Southbound NW Federal Highway/U.S. 1 between Sebastian Boulevard & Cleveland Street, in Sebastian, will have 1 of 3 lanes closed intermittently, with possible lane shifts, 9 a.m. to 4 p.m. Monday, October 5, through Friday, October 9, for FP&L utility operations. For more information, please contact Rafael Ureña at 772-882-5084.

###